BANGALORE DIVISION.

Notification dated 9th April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 2nd May 1936, for Restoring Chickanahalli Kamanahalli Kodagikere, Minor Tank Register No. 245 of Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees three hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Chickanahalli Kamanahalli Kodagikere, Minor Tank Register No. 245 of Hoskote Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities for Restoring Chickanahalli Kamanahalli Kodagikere Minor Tank Register No. 245 of Hoskote Taluk.

No.	Items of work.	Unit	Quantity	Rate	Rate in	
					Figures	Words
	BUND.			Rs. a. p.		
1	Clearing lantana jungle	Grade	21	1 0 0		
2	Cutting grips and toe trenches ..	,,	24	1 8 0		
3	Earthwork to bund including watering and tamping	C.yd.	11,875	0 3 6		
4	Turfing to slope of bund and watering till it grows	S.yd.	8,123	0 0 10		
5	New stone revetment	C.yd.	937	1 10 0		
6	Removing and resetting old stone work with new jelly	,,	105	0 14 0		
7	Providing and fixing new grade stones with bed slabs including figures chiselled and painted	Each	27	2 0 0		
8	Do Register and Date Stones including figures chiselled and painted	,,	1	4 0 0		
9	Do B.M. stones do ..	,,	2	3 0 0		
10	Do Gauge stones do ..	,,	1	15 0 0		
11	Do Index stones do ..	,,	27	0 12 0		

No.	Items of work	Unit	Quantity	Rate	Rate in Figures	Rate in Words
				Rs. a. p.		
	SLUICE.					
1	Earthwork cut opening the bund ..	C.yd.	60	0 3 0		
2	Removing and resetting stone revetment with new jelly	,,	7	0 12 0		
3	Stone jelly concrete in surki mortar ..	C.ft.	106	0 4 6		
4	Burnt brick in surki mortar ..	,,	193	0 4 9		
5	Plastering with surki mortar ..	Sqr.	2·10	3 8 0		
6	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	66	0 6 0		
7	Cutting orifice in slabs	Each	4	0 12 0		
8	Fixing C.I. pipes 6″ Dr. including conveying from Divisional Office, laying, etc., complete (Pipes supplied Departmentally)	R.ft.	27	3 0 0		
9	Refilling the earth got from cut opening the bund and consolidating ..	C.yd.	60	0 2 0		
10	Providing and fixing wooden plug with locking arrangements, etc., complete	Each	1	15 0 0		
11	Rough stone work new	C.yd	3	1 10 0		
	"WASTE WEIR"					
1	Earthwork excavation, forming bank with consolidation	C.yd.	87	0 3 6		
2	Burnt brick in surki mortar ..	C.ft.	226	0 4 9		
3	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft	111	0 6 0		
4	Joggle joints	Each	10	0 12 0		
5	Plastering with surki mortar ..	Sqr.	3·37	3 8 0		
6	Rough stone work new	C.yd.	25	1 10 0		

M. A. SRINIVASACHARI,
Executive Engineer.

KOLAR DIVISION.

REVISED TENDER NOTICE FORMS.

Notification dated 9th April 1936.

Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 11 A.M. on 9th May 1936.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, on payment of Rupee one for each form should be addressed to the Executive Engineer, Kolar Division, and should be superscribed as "Tender for Restoring Breached Naravalapalli Dadinavaddu, Register No. 783, Bagepalli Taluk". The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 300 (Rupees three hundred) in cash or Government Promissory Notes of Mysore Government bonds at face value or market value whichever is less as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract (cash amount will not carry any interest).

4. The tenders will be opened in the presence of such tenderers, who wish to be present on 9th May 1936. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the works in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.